


15:05:04771:00:00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 12, Twp. 13 Rge. 18 (E) (W)
Location as "NE/CNW&SW&" or footage from lines. S/ ~~NE~~ ~~NE~~ NE NE
Lease Owner Leo J. Dreiling Oil Company
Lease Name Staab "B" Well No. 3
Office Address Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 10-17-60 19
Application for plugging filed 10-17-60 19
Application for plugging approved 10-17-60 19
Plugging commenced 10-17-60 19
Plugging completed 10-17-60 19
Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3737' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Surface Pipe</u>				<u>8 5/8"</u>	<u>200'</u>	<u>-0-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rotary mud was used in filling up hole to a depth of 550' were 1st plug was set using 20 sacks cement and 2nd. plug was set at 180' using 15 sacks cement, 3rd plug was set at 40' using 10 sacks cement and filling up hole to top.

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. DREILING & SONS, INC.
Address VICTORIA, KANSAS

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling a partner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
Leo F. Dreiling
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1962

Ronald Zimmerman
Notary Public.

My commission expires August 14, 1965



L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company	Leo J. Dreiling Oil Company Victoria, Kansas	Sec. 12	Twp. 13	Rng. 18
Farm	Staab "B" No. 3	Location	S/W Q2-25 NE NE	
Total Depth	3737'	County	Ellis County	
Comm.	10-8-60	Comp.	10-17-60	Elevation: D. F. 2152'
Contractor	L. J. DREILING & SONS, INC. VICTORIA, KANSAS			G. R.
	Casing Record 8 5/8" - - - - 200'	Cement Record 150 sacks cement	Production:	D & A

Figures Indicate Bottom of Formations

0 - 40	Rock & Surface Clay
40 - 130	Shale
130 - 200	Shale & Shells
200 - 420	Shale
420 - 580	Sand
580 - 640	Shale
640 - 700	Shale
700 - 850	Shale & Sand
850 - 1060	Shale
1060 - 1245	Red Rock & Shale
1245 - 1403	Shale & Red Rock
1403 - 1430	Anhydrite
1430 - 1436	Anhydrite
1436 - 1840	Shale & Shells
1840 - 1910	Shale & Shells
1910 - 2145	Shale & Lime
2145 - 2345	Shale & Lime
2345 - 2420	Fort Riley Lime
2420 - 2515	Shale & Lime
2515 - 2635	Shale & Lime
2635 - 2740	Shale
2740 - 2865	Lime & Shale
2865 - 3035	Shale
3035 - 3140	Shale & Broken Lime
3140 - 3285	Lime
3285 - 3355	Lime
3355 - 3410	Lime
3410 - 3460	Lime
3460 - 3572	Lime
3572 - 3659	Lime
3659 - 3737	Lime
3737	TD

RECEIVED
STATE COMMISSION
AUG 22 1962
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report of the Staab "B" No. 3.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 17th day of August, 1962.

Ronald Zimmerman

NOTARY PUBLIC

My Commission Expires: August 14, 1965