

STATE OF KANSAS  
STATE CORPORATION  
COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-97536 <sup>03437-0000</sup>

LEASE NAME Colahan "B"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to  
Cons. Div. Office within  
30 days

WELL NUMBER #5

4290' Ft. from S Section Line

1650' Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC 25 TWP 11S RGE 17 or W

ADDRESS P.O. Box D - Plainville

COUNTY Ellis

PHONE# (913)434-7681 Operators License 5447

Date Well Completed 3/6/41

Character of Well Oil

Plugging Commenced 4/29/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/29/97

The plugging proposal was approved on 1/21/97 (Date)

by Dennis Hamel (KCC District Agent's name).

Is ACO-1 filed? On File If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3368' Bottom 3375' T.D. 3375'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		5'	1070'	8-5/8"	1065'	0'
		0'	3368'	5-1/2"	3368'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ Feet to \_\_\_\_\_ Feet each set.

\*\*\* See back for details \*\*\*

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. \_\_\_\_\_

Address P.O. Box 31 - Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc

STATE OF Kansas COUNTY OF Rooks, ss.

J.D. Hininger (Employee of Operator) or (Operator) of above-described well, being first duly worn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so held me God.

(Signature) J.D. Hininger


(Address) P.O. Box D, Plainville, KS 67663

SUBSCRIBED AND SWORN TO before me this 28<sup>th</sup> day of May, 19 97

Sheryl Axelson  
Notary Public

My commission Expires: 05/20/2000

Form CP-4  
REVISED 05-88



OXY U.S.A., Inc.  
Well Chronological Report

06/03/97

COLAHAN B 5

=====

05/02/97 JOB: Plug and Abandon; CMIC: Gary Wagner

04/29/97 - RU ran wireline and perf. 2 shots/ft. @ 1050ft. - 5 1/2"  
csg. mixed & pumped 25 sks. 60/40 cement - 10% gel - w/300# hulls - 10  
sk gel - 225 sk cement w/300# hulls @ 1000# Max PSI - shut in 500# - 8  
5/8 backside mixed & pumped 30 sk cement @ 600# PSI - shut in @ 400#  
KCC - Dennis Hamel

L/E \$ 1520; MAT \$ 2035; CUM: L/E \$ 1520, MAT \$ 2035;

06-14-97