

15-051-03445-0000
RECEIVED
STATE CORPORATION COMMISSION
12-31-97

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER DEC 31 1997
LEASE NAME Colahan B
WELL NUMBER SECTION DIVISION
Wichita, Kansas

TYPE OR PRINT
NOTICE: Fill out completely and return 660' ft. from S Section Line
to Cons. Div. office within 30 days. 4950' ft. from E Section Line

LEASE OPERATOR Oxy USA Inc.
ADDRESS P.O. Box D, Plainville, KS 67663
PHONE # 785-434-7681 OPERATOR'S LICENSE NO. 5447
Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply)

Spot Location _____
SEC 25 TWP 11S RGE 17 or (W)
COUNTY Ellis
Date Well Completed _____
Plugging Commenced 12-1-97
Plugging Completed 12-1-97

The plugging proposal was approved on 11-4-97 (date)
by Marvin Miller Hays, KS (KCC District Agent's Name)

Is ACO-1 filed? On File If not, is well log attached? _____

Producing Formation OH Arbuckel Depth to Top 3550' Bottom 3564' T.D. 3564'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORDS		
Formation	Content	From	To	Size	Put in	Pulled out
		5'	1140'	8-5/8"	1140'	0'
		0'	3550'	5-1/2"	3550'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

*** See back for details ***

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. NA
Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA INC.

STATE OF Kansas COUNTY OF Rooks, ss.
J.D. Hininger


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J.D. Hininger
(Address) P.O. Box D, Plainville, KS

SUBSCRIBED AND SWORN TO before me this 8th day of December 1997

Sherilyn Axelson Notary Public

My Commission Expires:
5-20-2000



OXY U.S.A., Inc.
Well Chronological Report

12/30/97

COLAHAN B 16
=====

12/26/97 JOB: Plug and Abandon; CMIC: George Younger
12/1/97 - Plug and Abandon - Rigged up and ran 2 1/2" tbg. to 1850'
Mixed and pumped 155 sks. 60/40 pozmix plus 10% gel and 500 lbs. hulls
- lost circulation - pulled tbg. to 1400 ft. - pumped 75 sks. same
cement and circulated to surface. - Pulled rest of tbg. and topped off
of 5 1/2" w/35 sks. State Witness Dennis Hamel - plugged 12/01/97 -
3:00 PM
12/22/97 - Topped off 5 1/2" w/30 sks. cement.
12/26/97 - Cut off csg. - cleaned up location. - complete
L/E \$ 333; MAT \$ 4337; CUM: L/E \$ 333, MAT \$ 4337;

RECEIVED
STATE OF KANSAS CONSERVATIONDEC 31 1997
12-31-97
CONSERVATION DIVISION
Wichita, Kansas