

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis

County Sec. **25** Twp. **11** Rge. (E) **17** (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines **NW NW SE**

Lease Owner **Cities Service Oil Company**

Lease Name **Colaban** Well No. **"B" 14**

Office Address **Bartlesville, Oklahoma.**

Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**

Date well completed **5-22-42** 19

Application for plugging filed **5-23-42** 19

Application for plugging approved **5-23-42** 19

Plugging commenced **5-23-42** 19

Plugging completed **5-23-42** 19

Reason for abandonment of well or producing formation **Dry**

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? **Yes**

Name of Conservation Agent who supervised plugging of this well **Mr. C.T. Alexander**

Producing formation **Arbuckle Lime** Depth to top **3497'** Bottom Total Depth of Well **3520'** Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle Lime	Dry			85/8"	1052'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud from total depth 3530' to 300' set plug dumped 15 sacks cement mud to 23' set plug dumped 10 sacks cement mud & dirt to surface.

pd.
6/23/42
Ha

PLUGGING
FILE SEC 25 11, 17W
BOOK PAGE 35 LINE 31

RWD
09-03-42

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to **Mr. R.C. Hauber**
Address **Cities Service Oil Company Great Bend, Kansas.**

STATE OF **Kansas**, COUNTY OF **Barton**

Mr. J.A. Cleverley (employee of owner) or **owner or operator** of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J.A. Cleverley*

Cities Service Oil Co. Russell, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this **28** day of **May** 19**42**

My commission expires Sept. 26, 1942

C. B. Kirby
Notary Public.

My commission expires



WELL RECORD

15-051-03641-0000

Company Citizen Service Oil Co. Well No. 11 Farm Colahan #2
 Location 330' south and 330' east of Center Sec. 25 T. 11 R. 17N
 Elevation 1921 County Illia State Kansas
 Drlg. Comm. May 7, 1942 Contractor Huber Oil & Gas Company
 Drlg. Comp. May 23, 1942 Acid None
 T. D. 3530' Initial Prod. dry - plugged and abandoned

CASING RECORD:
 8-5/8" @ 1000' con. 300 ex Lams Star
 and 300' G. C.

FORMATION RECORD:

shale & shells	0-280
sand	280
shale & shells	330
sand	610
shale & shells	660
sand	780
red bed & shale	1000
red bed, shale & shells	1082
red bed & shale	1108
anhydrite	1145
red bed & shale	1425
salt & shale	1660
salt & shells	1680
shale & shells	1800
lime	1905
shale	1932
lime broken	2019
lime	2045
lime broken	2133
lime & shale	2500
shale & shells	2832
lime (lost returns @ 3110)	3140
shale	3153
broken lime	3200
lime	3215
broken lime	3448
conglomerate	3475
coared lime (rec. 1 1/2')	3483
lime & chert	3530 ft. 2.

Proximal Arbuckle 3467'
 Arbuckle 3490'
 Penetration 32'
 Total Depth 3530'

Depth: 300' 00
 1000' 00
 1500' 00
 2000' 00
 2500' 00
 3000' 00

PLUGGING
 FILE SEC. 25 T. 11 R. 17N
 BOOK PAGE 35 LINE 31

RECORDED
 09-03-42