


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Ellis County, Sec 25 Twp 11S Rge. (E) 17 (W)
Location as "NE/CNWxSWx" or footage from lines SW NW NW
Lease Owner Cities Service Oil Company
Lease Name Colahan "B" Well No. 1
Office Address Box 553 Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 8-24 19 40
Application for plugging filed 11-12 19 71
Application for plugging approved 11-15 19 71
Plugging commenced 2-2 19 72
Plugging completed 3-2 19 72
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production December 19 70
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey
Producing formation Arbuckle Depth to top 3555' Bottom 45' Pen. Total Depth of Well 3600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1110'	None
				5 1/2"	3555'	1096'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed 5 1/2" plug to 3250', dumped sand 3250 to 3240' and 5 Sx.
Cement 3240' to 3204'. 5 1/2" casing was parted - pulled 35 Joints.
Halliburton pumped 20 sx. gel, 3 sx. hulls 1225' to 525', 8 5/8" plug,
105 Sx. Cement 525' to surface.


RECEIVED
STATE CORPORATION COMMISSION
APR 7 1972
CONSERVATION DIVISION
Wichita, Kansas
04-07-72

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
E. W. Peterman (employee of owner) or (owner of the well) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. W. Peterman
Box 553 Russell, Kansas 67665
(Address)

Sworn to before me this 5th day of April, 19 72



10-5-72

Notary Public.

WELL RECORD

15-051-03434-0000

Company Cities Service Oil Co. Well No. #1 Farm Colahan "B"
 Location 330' east & 990' south of NW Cor. Sec. 23 T. 11 R. 17-W
 Elevation 2079 County Ellis State Kansas
 Drlg. Comm. July 21, 1940 Contractor Mabeo Oil & Gas Company
 Drlg. Comp. August 24, 1940 Acid 2000 gals. 8-21-40; 4000 gals. 8-27-40.
 T. D. 3600 Initial Prod. Echo-Meter Potential: 2420 oil, no water, 24 hrs.

CASING RECORD:

8-5/8" @ 1110' cem. 325 sx Atlas and
 10 sx Aquagel; recem.
 top 215' with 145 sx cem.
 5-1/2" @ 3535' cem. 100 sx Atlas

Corr. Top Arbuckle 3535 -1476
 Penetration 45'
 Total Depth 3600

FORMATION RECORD:

rock and shale	0-70
shale	360
shale & sand	393
shale & shells	500
sand	560
shale & red bed	730
sand	830
sand & shale	950
shale & shells	1110
red bed & shale	1250
anhydrite	1280
lime	1290
red bed & shell	1450
shale & shells	1605
shale, salt & red bed	1685
shale & salt	1800
shale & shells	1900
shale & lime	2024
lime broken	2130
shale	2165
lime	2202
lime broken	2251
lime	2309
lime broken	2328
lime & shale	2463
lime	2515
lime & shale	2638
shale & shells	2969
lime (lost circ. @ 3544)	3544
lime broken	3558
lime cored (rec. 3')	3558

FILLUP: 150' oil in 1 hr. @ 3562
 200' oil in 1 1/2 hrs. @ 3562
 1075' oil in 2 1/2 hrs. @ 3566
 2500' oil in 4 1/2 hrs.
 2575' oil in 5 1/2 hrs.
 2675' oil in 6 1/2 hrs.

Jetted 500 gals. acid 8-21-40.

SIFO: 1000' 00
 1500' 00
 2000' 10
 2500' 00
 3000' 00

RECEIVED
 STATE CONSERVATION COMMISSION
 NOV 15 1971
 CONSERVATION DIVISION
 Wichita, Kansas

11-15-71

Rotary T.D. 3558 = 3559 S.L.M.
 lime 3559-3600 T.D.