

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051 21363-00-00

LEASE NAME G. E. Riedel

WELL NUMBER 13

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from (S) Section Line

1650 Ft. from (E) Section Line

SEC. 31 TWP. 13 SRGE. 19 (E) or (W)

COUNTY Ellis, Kans.

LEASE OPERATOR Brook Oil & Gas Corp.

ADDRESS 15 th. & Vine St. Dean Ellmer Bldg.
Suite 2 Hays, Kans. 67601

PHONE (913) 628-1909 OPERATORS LICENSE NO. 4694

Date Well Completed 10-26-77

Plugging Commenced 8-12-92

Plugging Completed 8-12-92

Character of Well _____

(OIL) Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-9-92 (date)

by David P. Williams Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Arbuckle Depth to Top 3878 Bottom 3882

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arb.	Oil & Water	0	1496	8 5/8	1496	0
		0	3878	5 1/2	3878	0

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1992

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Ran 2 7/8" tbg. to 3800'. Pump 155 SKS 65-35 POZ-Mix 8% gel & 300# bulk
Plug from 1500' to 3800'. Pull out to 1500'. Pump 100 SKS 65-35 POZ-Mix
8% Gel 200# Hulls Cement Circulated. P.O.H. Pump 10 SKS 65-35 POZ Mix
8% Gel into 8 5/8 x 5 1/2 Annulus, pressured to 700# held. ST (over)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address P.O. Box 428 Hays, Kans.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brook Oil & Gas Corp.


STATE OF Kans. COUNTY OF Ellis, ss.

Ted C. Luehbers (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ted Luehbers

(Address) Hays, Kans

SUBSCRIBED AND SWORN TO before me this 28 day of Sept, 1992



C.C. Schumacher
Notary Public

My Commission Expires: 4-15-96

Tie onto 5 1/2" pump 15 SRS 65-35 Poz. Mix 8% Gel. Pressured
to 400" held S.I. Cut off 5 1/2" and weld on plate.