

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

150570285700000

API NUMBER 11-8-52

LEASE NAME G.E. Riedel

WELL NUMBER 4

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 31 TWP. 135 RGE. 19 (E) or (W)

COUNTY Ellis

Date Well Completed 11-8-52

Plugging Commenced 10-14-92

Plugging Completed 10-14-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Brock Oil & Gas Corp.

ADDRESS 25th & Vine St. Dean Ellner Bldg. Suite 2
Hays, Kans. 67601

PHONE#(913) 628-1909 OPERATORS LICENSE NO. 4694

Character of Well Oil

(O), Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-9-92 (date)

by David P. Williams Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? No Do not have

Producing Formation ARB Depth to Top 3905 Bottom 3912 T.D. 3912

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
ARB	Oil & Water	3905	12	10 3/4	241	None
				7	3905	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Ran Halliburton Slick line to 3910'. MIBU Halliburton, Tie onto 10 3/4 x 7 Annulus,
Pump 100 SKS 65-35 Poz-Mix 8% Gel. 200" Max. 100" S.I. Tie onto 7" CSG.
Pump 475 SKS 65-35 Poz-Mix 8% Gel. 450" Hulls. 800" Max. 200" S.I. Tie onto
10 3/4 x 7 Annulus, pump 25 SKS 65-35 Poz-Mix 8% Gel. 50" Hulls 350 Max. 150" S.I. 2:15 PM.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address P.O. Box 428 Hays, Kans. 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brock Oil & Gas Corp.

STATE OF Kans. COUNTY OF Ellis, ss.

Ted Luebbers (Employee of Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ted Luebbers


(Address) 1725 Volga Apt C Hays, Kans.

SUBSCRIBED AND SWORN TO before me this 9 day of Dec, 19 92

C.C. Schumacher

Notary Public

My Commission Expires: 4-15-96



Form CP-1
 Revised 05-81

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 11 1992