

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-5-117

15-157-05333-00-00

API NUMBER 3-5-53

LEASE NAME G.E. Riedel

WELL NUMBER 6

990 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 31 TWP. 13S RGE. 19 (E) or (W)

COUNTY Ellis

Date Well Completed 3-5-53

Plugging Commenced 4-21-93

Plugging Completed 4-21-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Brook Oil & Gas Corp.

ADDRESS 25th & Vine St. Dean Ellner Bldg. Suite 2
Hays, Kans. 67601

PHONE (913) 628-1909 OPERATORS LICENSE NO. 4694

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-31-93 (date)

by David P. Williams, Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No do not have

Producing Formation Arbuckle Depth to Top 3897 Bottom 3908 T.D. 3846 P.B.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Arbuckle</u>	<u>oil & water</u>	<u>Surf.</u>	<u>278'</u>	<u>10 3/4"</u>	<u>278'</u>	<u>None</u>
		<u>Surf.</u>	<u>3897</u>	<u>7"</u>	<u>3897</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Perforate at 2200, 1520, 877. Run 2 7/8" TBG to 3750. Pump 200 SKS. 6.5-35 Poz-Mix 10% gel 300# HULLS. P.O.H. to 1980'. Pump 425 SKS. 6.5-35 Poz-Mix 10% Gel 200# HULLS. P.O.H. to 900'. Pump 115 SKS. 6.5-35 Poz-Mix 10% Gel 450# HULLS. Cement circulated. P.O.H. w/ TBG. (over)
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rapid Well Serv. License No. 27649

Address P.O. Box 208 Russell, Kans. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brook Oil & Gas Corp.

STATE OF Kans COUNTY OF Ellis, ss.


Ted Luehbers (Employee of Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Ted Luehbers

(Address) Hays, Kans. 67601

SUBSCRIBED AND SWORN TO before me this 25th day of April, 19 93



[Signature]
 Notary Public

My Commission Expires: 3-2-97

RECEIVED
 KANSAS CORPORATION COMMISSION
 MAY 25 1993
 05-25-93
 CONSERVATION DIVISION
 WICHITA, KANSAS

Tie onto 10³/₄" x 7" Annulas. Pump 40 SKS 65-35 Poz-Mix 10% gel

50# Halls 200# Max. Fill 7" w/10 SKS " " " " " "

Well P.A 1:50 P.M. 4-21-93 KCC Rep Marion Schmidt on location