

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-057-05/25-00-00
WELL PLUGGING RECORD

Ellis County, Sec. 31 Twp. 13 Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE NE

Lease Owner A. F. Schmidt

Lease Name Riedel Well No. 1

Office Address Box 662 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed January 1, 19 58

Application for plugging filed November 2, 19 59

Application for plugging approved November 2, 19 59

Plugging commenced November 6, 19 59

Plugging completed November 6, 19 59

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Eldon Petty

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3923' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8 5/8 " at 260' circulated with cement - 5 1/2" 3920' with 100 sacks cement. Filled with sand to 3900', set 4 sacks cement with dump bailer, pulled 3215' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" at 600' (20 sacks Gel), displaced 20 sacks cement through 5 1/2" at 600', heavy mud to 200', displaced 20 sacks cement through 5 1/2" at 200', heavy mud to 35', set bridge and 10 sacks cement to bottom of cellar.

Mudding and cementing by Pump truck.

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1966

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling
Address Ellinwood, Kansas #236
08-05-66
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
A. F. Schmidt (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. F. Schmidt

P.O. Box 662 Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 4th day of August 19 66

My commission expires June 22nd 1969

James E. Rudke
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- ROCKET DRILLING COMPANY, INC.
Farm- Riedel No. 1

15-051-05125-00-00

SEC. 31 T. 13 R. 19W
NE SE NE

Total Depth. 3923'
Comm. 12-17-57 Comp. 1-1-58
Shot or Treated.
Contractor. Bennett & Roberts Drilling Company
Issued. 3-1-58

County Ellis
KANSAS



CASING:
8 5/8" 248' cem w/150 sx
5 1/2" 3920' cem w/100 sx

Elevation. 2267'

Production. 25 BOPD

Figures indicate Bottom of Formations.

chalk rock	30
shale & shells	230
shale	420
shale & clay w/sand streaks	775
shale	930
red bed	1050
sand	1240
shale	1255
shale, shells, red bed	1555
Anhydrite	1607
shale & shells	1850
shale & lime	3486
chalky lime	3494
lime	3523
shale	3528
lime & shale	3538
lime	3825
lime & shale	3880
lime, conglomerate	3895
Conglomerate	3918
lime	3922-RTD
lime	3923-CTD
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1966

CONSERVATION DIVISION
Wichita, Kan.

TOPS:	
Anhydrite	2552
Topeka Lime	3269
Heebner Shale	3524
Toronto Lime	3545
Lansing-Kansas City	3565
Base Kansas City	3823
Cherty Conglomerate	3878
Arbuckle	3919