

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-051-02838-0000

API NUMBER 1-31-53

LEASE NAME G. E. Riedel

WELL NUMBER 5

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 31 TWP. 13S RGE. 19 (E) or (W)

COUNTY Ellis

Date Well Completed 1-31-53

Plugging Commenced 4-21-93

Plugging Completed 4-21-93

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Brock Oil & Gas Corp.

ADDRESS 25th & Vine St. Dean Ellner Bldg. Suite 2  
Hays, Kans. 67601

PHONE# (913) 628-1909 OPERATORS LICENSE NO. 4694

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-31-93 (date)

by David P. Williams, Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No do not have

Producing Formation Arbuckle Depth to Top 3905 Bottom 3913 T.D. 3913

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil & Water	Surf.	278'	10 3/4"	278'	None
		Surf.	3905	7"	3905	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from    feet to    feet each set  
Perforate at 2200', 1500', 873'. Ran 2 7/8" T&G. to 3800'. Pump 200 SKS  
65-35 Poz. Mix. 10% Gel 300" HULLS. P.O.H. to 1980'. Pump 250 SKS 65-35  
Poz-Mix 10% gel 200" HULLS. Cement circulated. P.O.H. tie onto 10 3/4 x 7"  
Annular. Pump 50 SKS. 65-35 Poz-Mix 10% Gel, 300" Max. (Over)  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rapid Well Serv. License No. 7049

Address P.O. Box 208 Russell, Kans. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brock Oil & Gas Corp.


STATE OF Kans. COUNTY OF Ellis

Ted Luebbers (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) Ted Luebbers

(Address) Hays, Kans. 67601



SUBSCRIBED AND SWORN TO before me this 25th day of May, 19 93

My Commission Expires: 3-8-97

Notary Public

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 MAY 25 1993 OS-25-93

Fill 7" CSG. W/30 SKS 65-35 Poz-Mix 10% Gel. P.A

6:15 P.M. 4-21-93 KCC Rep. Marion Schmidt on location