

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-051-05382-0000

API NUMBER 3-26-52

LEASE NAME G. E. Riedel

WELL NUMBER 2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

1650 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 31 TWP. 13S RGE. 19 (E) or (W)

COUNTY Ellis

LEASE OPERATOR Brock Oil & Gas Corp.

ADDRESS 25 th. & Vine St. Dean Ellner Bldg Suite 2
Hays, Kans. 67601

PHONE#(913) 628-1909 OPERATORS LICENSE NO. 4694

Date Well Completed 3-26-52

Character of Well oil

Plugging Commenced 4-22-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-22-93

The plugging proposal was approved on 3-31-93 (date)

by David P. Williams, Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No do not have

Producing Formation Arbuckle Depth to Top 3878 Bottom 3888 T.D. 3888

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------------|-------------------|--------------|-------------|---------------|-------------|-------------|
| <u>Arbuckle</u> | <u>Oil, Water</u> | <u>Surf.</u> | <u>645</u> | <u>8 5/8"</u> | <u>645</u> | <u>None</u> |
| | | <u>Surf.</u> | <u>3884</u> | <u>5 1/2"</u> | <u>3884</u> | <u>None</u> |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Ran 2 7/8" TBG to 2100', perforate w/ thru tbg. gun at 2200'. Ran 2 7/8" tbg. to 3750'. Pump 150 SKS. 6.5-35 Poz Mix and 100" HULLS. 10% Gel. Pull tbg. to 1540'. Pump 115 SKS 6.5-35 Poz Mix 10% gel + 100" HULLS. Cement circulated. POH w/ TBG. Tie onto 8 5/8" x 5 1/2" Annulus. (Over)
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rapid Well Serv. License No. 7049

Address P.O. Box 208 Russell, Kans. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brock Oil & Gas Corp.


STATE OF Kans. COUNTY OF Ellis

Ted Luebbers (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ted Luebbers

(Address) Hays, Kans. 67601



SWORN TO before me this 25th day of May, 1993

Richard Huden
 Notary Public

My Commission Expires: 3-8-97

Pump 50 SXS 65-35 Poz Mix 10% Gel 100" Halls. Max press 300".

Fill 5 1/2" csg. w/ 20 SXS 65-35 Poz Mix 10% Gel. Well P.A.

6:45 P.M. 4-22-93 KCC Rep. Marion Schmidt on Location.