

15-051-05893-00-00



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 7 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Thornton Anderson

Complete Address Suite 746, 300 W. Douglas, Wichita, Kansas 67202

Lease Name Rumsey Well No. 29

Location NE SE NE Sec. 23 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3423'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 2:30 P Day 6 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 3423' 13" csg 138' cwc 125 sx. 8 5/8 csg 1120' cwc 325 sx.

4 1/2 csg 3414' cw 100 sk cem. & perf. (3413)

Filled 4 1/2 csg W/sd (3423-3400) dumped 4 sk cem W/dump bailer. (3400-3365)

Cutoff & recovered 2220' of 4 1/2 csg.

Drlg. mud to 450' -set rock & sand bridge (450-425)

Filled with RM cem. from 425 to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 3/11/75

INV. NO. 953-W