

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

02-04-75  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Thornton E. Anderson  
Complete Address Suite 746, 300 W. Douglas, Wichita, Kansas 67202  
Lease Name J.L. Rumsey Well No. 24  
Location NW NE NE Sec. 23 Twp. 11 Rge. (E) (W) 17  
County Ellis Total Depth 3437'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Pipe Pullers, Inc.  
Address Box 486, Ellinwood, Kansas 67526 License No. 462  
Operation Completed: Hour 11 A Day 1 Month 2 Year 1975

The above well was plugged as follows:

Total Depth 3437' 13" csg set 126' cwc 125 sk. 8 5/8 csg set 1105' cwc 315 sx.  
4 1/2 csg set at 3428' cw 100 sk cmt. & perf. (3405')  
Filled 4 1/2 csg W/sd (3437-3400) dumped 4 sk cmt W/dump bailer. (3400-3365)  
Pushed 4 1/2 wood plug to 3400' -poured 50' sd -dumped 4 sk cmt W/dump bailer. (3100-3020)  
Cutoff & recovered 2810' of 4 1/2 csg.  
Filled 8 5/8 csg with mud to 450' set rock & sand bridge (450-440)  
Filled with RM cement from 440' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo B. Messer  
Well Plugging Supervisor

DATE 2/5/75  
INV. NO. 772-W