



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

MAR 3 1975
03-03-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thornton E. Anderson
Complete Address Suite 746, 300 W. Douglas, Wichita, Kansas 67202
Lease Name J.L. Rumsey Aug YCC Well No. 22
Location SW SE NE Sec. 23 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3439'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas 67526 License No. 462
Operation Completed: Hour 2 P Day 27 Month 2 Year 1975

The above well was plugged as follows:

Total depth 3439' 13" csg 126' cwc 150 sx. 8 5/8 csg 1154' cwc 325 sx.
4 1/2 csg 3430' cw 100 sx cem. & pFS (3429)
Set 4 1/2 wood plug 3400' -poured 20' sd -dumped 3 sk cem W/dump bailer. (3400-3350)
Cutoff & recovered 2326' of 4 1/2 csg.
Filled 8 5/8 csg W/mud to 500' -set rock & sand bridge (500-490)
Filled with RM cem. from 490' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Reo Z. Massey
Well Plugging Supervisor

DATE 3/5/75
INV. NO. 912-W