



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Rumsey "A" Well No. 17

Location C SW SE Sec. 23 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3486'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 4 P Day 28 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3486' 8 5/8 csg set at 1067' cwc 500 sk.

5 1/2 csg set at 3481' cw 175 sk cmt.

5 1/2 csg FBTD 3402' with top perf. (3172')

Set 5 1/2 wood plug at 3150' -poured 10' sd -dumped 5 sk cmt W/dump bailer. (3100-3150)

Cutoff and recovered 2400' of 5 1/2 csg.

Pumped down 8 5/8 csg with 14 sk gel & water, released plug and pumped 160 sk

hulls and 90 sk cmt. (Halib. Lite) PSI 350

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 1-10-72

INV. NO. 4902-W