

15-051-03397-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company
Complete Address Box 553 Russell, Kansas 67665
Lease Name Rumsey "A" Well No. 14
Location SW SE SE Sec. 23 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3510'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 5 P Day 28 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3510' 8 5/8 csg set at 1067' cwc

5 1/2 csg set at 3504' cw 100 sk cmt.

Filled 5 1/2 W/sd (3487-3510) Dumped 5 sk cmt W/dump bailer. (3450-3487)

Recovered ~~1080'~~ of 5 1/2 csg.

Pumped down 8 5/8 csg with 12 sk gel & water, released plug and pumped 100 lbs

hulls and 105 sk cmt. (35-65) W/6% total gel. PSI 300

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 1-10-72

INV. NO. 4901-W