

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 7 1959
5-7-59
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 29-7 County: Ellis

Location: NW NE NW Sec. 23 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3368

I have this date completed supervision of plugging of:

Lease Name: J.L. Rumsey AND CC Well No. 9

Operator's Full Name: Shell Oil Co

Complete Address: Box 744 Great Bend, Kans

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kans License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 26 Month 4 Year 59

The above well was plugged as follows:

16" at 134' circulated with cement - 10 3/4" 1093' circulated with cement
7" 3358' with 200 sax cement.

Filled with sand to 3340', set 5 sax cement with dump bailer, pulled 2300'

7" to 500', circulated hole with heavy mud through 7" (Gel), displaced

30 sax cement through 7" at 450', heavy mud to 160', displaced 30 sax cement
through 7" at 160', heavy mud to 30', set bridge and 10 sax cement to bottom
cellar.

Mudding and cementing by Forbes Co pump truck/

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC 29 T. 11 R. 17
BOOK PAGE 29 LINE 2