

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

OCT 16 1959
10-16-59
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 56-17 County: Ellis

Location: SW NE NW Sec. 23 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3383

I have this date completed supervision of plugging of:

Lease Name: J.L. Rumsey A.B. KCL Well No. 10

Operator's Full Name: Shell Oil Co

Complete Address: Box 744 Great Bend, Kans

Plugging Contractor: Forbes Casing Pulling

Address: Great Bend, Kans License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 13 Month 10 Year 59

The above well was plugged as follows:

16" at 132' circulated with cement - 10 3/4" 1092' circulated with 350 sax ce-
ment, 7" 3367' with 200 sax cement.

Filled with sand to 3350', set 5 sax cement with dump bailer, pulled

2375' 7" to 500', circulated hole with heavy mud through 7". (38 sax Gel)

displaced 30 sax cement through 7" at 500', heavy mud to 180', displaced

30 sax cement through 7" at 180', heavy mud to 35', set bridge and 10 sax

cement to bottom cellar.

Mudding and cementing by Forbes Co pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 1/14/60
INV. NO. 654-w