

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 93-5

LOCATION SW ^{NW} SE
AND

SEC. 23 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease Rumsey

Operator Cities Service Co Address Great Bend, Kans

Field Bemis County Ellis

Total Depth 5416 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 1054' circulated with 525 sax cement - 7" at 5407' with
150 sax cement behind .

Filled with sand to 5400', set 5 sax cement with dump bailer,
pulled 2775' 7", filled with mud to 500', set rock and 20 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
WELL NO. 23 T 11 R 17 W
SEC. 23 TWP. 11 RGE. 17
DATE 6-23-53

RECEIVED
CONSERVATION DIVISION
06-24-53
WICHITA, KANSAS

Edson Petty
District Conservation Agent
Date 6-23-53