

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company
Complete Address Box 553 Russell, Kansas 67665
Lease Name Rumsey "A" Well No. 6
Location NW SW SE Sec. 23 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3547'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 2:30 P Day 28 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3547' 10 3/4 csg set at 998' cwc 500 sk.
7" csg set at 3410' cw 150 sk cmt.
5 1/2 liner set (3348-3347') cemented.
5 1/2 PBD 3460' and perf. (3440)
Set wood plug at 3348' -poured 10' sd -dumped 7 sk cmt W/dump bailer. (3301-3348)
Cutoff and recovered 1676' of 7" csg.
Pumped down 10 3/4 csg with 20 sk gel \$ water, released plug and pumped 100 lbs hulls
and 135 sk cmt. (35-65) 6% total gel. PSI 350

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 1-10-72
INV. NO. 4900-W