

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 29 1959
CONSERVATION DIVISION
Wichita, Kansas

10-29-59

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 56-16 County: Ellis

Location: NW SE NW Sec. 23 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3460

I have this date completed supervision of plugging of:

Lease Name: J.L. Rumsey AUBXC Well No. 11

Operator's Full Name: Shell Oil Co

Complete Address: Box 744 Great Bend, Kans

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kans License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 22 Month 10 Year 59

The above well was plugged as follows:

16" at 128' circulated with cement - 10" 1097' circulated with cement -
7" 3365' with 200 sax cement behind - 5 1/2" liner 3303' to 3455' - 2" tubing
lost in hole, top of tubing 3308'.

Filled with sand to 3300', set 5 sax cement with dump bailer, pulled 2420'
7" to 875', circulated hole with heavy mud through 7" at 875' (33 sax Gel)
Displaced 30 sax cement through 7" at 500', heavy mud to 180', displaced
30 sax cement through 7" at 180', heavy mud to 35', set rock and 10 sax
cement to bottom cellar.

Mudding and cementing by Forbes Co pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 1/14/60
INV. NO. 629-W