

15-051-05860-0001



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
02-04-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thornton E. Anderson
Complete Address Suite 746, 300 W. Douglas, Wichita, Kansas 67202
Lease Name Rumsey Well No. 12
Location SW SE NW Sec. 23 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth ~~3421~~ 3390'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas 67526 License No. 462
Operation Completed: Hour 4 P Day 27 Month 1 Year 1975

The above well was plugged as follows:

- Total Depth 3421' 16" csg 129' cwc 150 sx. 10 3/4 csg 1095' cwc 350 sk.
- 7" csg 3371' cw 200 sk cem.
- 5" liner set (3346-3421) cw 75 sk cem. with top perf. (3370)
- Set wood plug at 3346' (top of liner) dump 6 sk cmt W/dump bailer. (3346-3316)
- Cutoff & recovered 2525' of 7" csg.
- Filled 10 3/4 csg with mud to 415' -set rock & sand bridge (415-400)
- Filled with RM cem. from 400' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 2/5/75
INV. NO. 771-W