

15-051-03399-0001

Form CP-3  
Rev. 6-4-68

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 11 1972  
08-11-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Rumsey "A" Well No. 16

Location SE NW SE Sec. 23 Twp.  Rge. 11 (E) (W) 17

County Ellis Total Depth ~~3537~~ 3554'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 12:30 P Day 10 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 3554' 8 5/8 csg set at 1197' cwc 600 sk

5 1/2 csg set at 3553' cw 100 sk cmt.

5 1/2 csg PBD 3537' with top perf. (3518)

Filled 5 1/2 csg with sand (3500-3537) dumped 5 sk cmt W/dump bailer.

Cutoff and recovered 2500' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -released 8 5/8 plug

and pumped 100 sk "Halib.- Light" cmt. Max. pres. 500 lbs. SI pres. 300 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Ben G. Murrup  
Well Plugging Supervisor

INVOICED  
DATE 8/11/72  
INV. NO. 0151-14