
KANSAS STATE CORPORATION COMMISSION





TO: Jewel M. Ogden, Director 500 Insurance Building 212 North Market Wichita 2, Kansas

File No. County: Ellis
Location SW SW NW Sec. 23 Twp. 11 Rge. 17 (E) (W)
Name of Field: Bemis Total Depth: 3435
I have this date completed supervision of plugging of:
Lease Name: JL, Rumsey Well No. 5
Operator's Full Name: Shell Oil Co
Complete Address: Box 744 Great Bend, Kans
Plugging Contractor: Forbes Pipe Pulling Co
Address: Great Bend, Kans License No. 49
Oil Well x Gas Well Input Well SWD Well D & A
Other Well as hereafter indicated:
Was any delay in plugging operations caused by Conservation Division Agent? Yes No x
If yes how long? Reason:
Operation Completed: Hour 5PM Day 15 Month 1 Year 60
The above well was plugged as follows:
10 3/4" 1096' circulated with 450 sax cement - 7" 3374' with 125 sax cement.
Filled with sand to 3360', set 5 sax cement with dump bailer, pulled 2612'
7" to 600', circulated hole with heavy mud through 7" at 600', (30 sax Gel)
displaced 30 sax cement through 7" at 500', heavy mud to 200', displaced 30
sax cement through 7" at 200', heavy mud to 35', set rock bridge and 10 sax
cement to bottom cellar.
Mudding and cementing by Forbes Co's pump truck.
Reviewed: Signed: Conservation Division Agent
Remarks: NVOICED
DATE 1/29/60
INV. NO. 854-W