

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 25 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mc Adams Pipe & Supply

Complete Address: 2700 Main Great Bend, Kansas

Lease Name Runsey Well No. 6

Location SE NW NW Sec. 23 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3367

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Pipe Pullers Inc

Address: Ellinwood, Kansas License No. 462

Operation Completed: Hour 11AM Day 21 Month 6 Year 63

The Above well was plugged as follows:

16" 194' circulated with cement - 10" 1083' with 400 sax cement - 7" 3350' with 125 sax cement.

Filled with sand to 3340', set 5 sax cement with dump bailer - pulled 2510' 7" to 915' circulated hole with heavy gel mud through 7" at 915' pulled 7" to 480', displaced 25 sax cement through 7" at 480', heavy mud to 180', displaced 25 sax cement through 7" at 180', heavy mud to 30', cement to bottom cellar.

Mudding and cementing by Pipe Pullers pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/26/63

INV. NO. 7320 W

Signed: [Signature]
Well Plugging Supervisor