

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: SW SW SE 23 Sec. 11 Twp. 17 Rge. \_\_\_\_\_ (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3441

I have this date completed supervision of plugging of:

Lease Name: Rumsey Well No. 7

Operator's Full Name: Cities Service Oil Co

Complete Address: Cities Service Bldg Bartlesville, Okla

Plugging Contractor: C. E. Shull

Address: Great Bend, Kans License No. 8

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4PM Day 6 Month 8 Year 60

The above well was plugged as follows:

8 5/8" 1000' circulated with cement - 5 1/2" 3435' with 100 sax cement.  
Set 5 sax cement on bottom with dump bailer, pulled 2300', 5 1/2" to 550',  
circulated hole with heavy mud through 5 1/2" ( 25 sax Gel), displaced 20 sax  
cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement  
through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax cement to  
bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: *Edson Terry*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

RECEIVED  
STATE CORPORATION COMMISSION  
DATE 8/26/60  
AUG 2 1960  
NO. 1394-U  
CONSERVATION DIVISION  
Wichita, Kansas