

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: NE SW SE Sec. 23 Twp. 11 Rge. 17 (E) (W)

Name of Field: Bemis Total Depth: 3443

I have this date completed supervision of plugging of:

Lease Name: Rumsey Well No. 8

Operator's Full Name: Cities Service Pet Co

Complete Address: Box 533 Russell, Kansas

Plugging Contractor: C. E. Shull

Address: Great Bend, Kansas License No. 8

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6PM Day 15 Month 2 Year 61

The above well was plugged as follows:

8 5/8" 997' circulated with 300 sax cement - 5 1/2" 3440' with 100 sax cement.

Filled with sand to 3400', set 4 sax cement with dump bailer, pulled 2450'

5 1/2" to 425', circulated hole with heavy mud through 5 1/2" at 425' ( 18 sax Gel),

displaced 20 sax cement through 5 1/2" at 425', heavy mud to 160', displaced

20 sax cement through 5 1/2" at 160', heavy mud to 35', set bridge and 10 sax

cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: Leon Petty  
Conservation Division Agent

Reviewed: Dyall-C-Phirk  
Field Supervisor

Remarks:

INVOICED  
DATE 3/2/61  
INV. NO. 2720-w

RECEIVED  
02-23-61  
CONSERVATION DIVISION