

2

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

JUN 20 1961  
CONS. DIVISION  
W. KANSAS

File No. \_\_\_\_\_ County: Ellis

Location: SE SW NW Sec. 23 Twp. 11 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 17

Name of Field: \_\_\_\_\_ Total Depth: 3469

I have this date completed supervision of plugging of:

Lease Name: J.L. Rumsey Well No. 8

Operator's Full Name: Great Bend Pipe & Supply

Complete Address: Drawer ( B ) Great Bend, Kansas

Plugging Contractor Forbes Casing Pulling Co

Address: Great Bend, Kansas License No. 49

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6PM Day 11 Month 6 Year 61

The above well was plugged as follows:

16" 136' circulated with cement - 10 3/4" 1096' circulated with cement.  
7" 3348' - 4 1/2" liner 161'  
Filled with sand to 3000', set 5 sax cement with dump bailer - pulled  
2700' 7" to 450', circulated hole with heavy mud through 7" (.35 sax Gel),  
displaced 20 sax cement through 7" at 450', heavy mud to 170', displaced  
20 sax cement through 7" at 170', heavy mud to 30', set bridge and 10  
sax cement to bottom cellar.

Mudding and cementing by Forbes Company pump truck.

Signed: Edon Petty  
Conservation Division Agent

Reviewed: Israel Albeis  
Field Supervisor

Remarks:

INVOICED  
DATE 6/23/61  
INV. NO. 3272-W