

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
AUG 17 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis
Location: NW NW SE Sec. 23 Twp. 11 Rge. 17 (E) (W)
Name of Field: _____ Total Depth: 3398

I have this date completed supervision of plugging of:

Lease Name: Rumsey Well No. 9
Operator's Full Name: Cities Service Co
Complete Address: Cities Service Bldg Bartlesville, Okla
Plugging Contractor: C. E. Shull
Address: Great Bend, Kans License No. 8
Oil Well Gas Well Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____
Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No
If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 11 Month 8 Year 60

The above well was plugged as follows:

8 5/8" 1020' circulated with cement - 5 1/2" 3391(with 100 sax cement.
Set 5 sax cement on bottom with dump bailer, pulled 2650' 5 1/2" to 510',
circulated hole with heavy mud through 5 1/2" at 510' (17 sax gel), displaced
20 sax cement through 5 1/2" at 510', heavy mud to 160', displaced 20 sax
cement through 5 1/2" at 160', heavy mud to 35', set bridge and 10 sax cement
to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INDEXED
DATE 8/26/60
INV. NO. 1795-W