

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis
Location: NE SE NW Sec. 23 Twp. 11 Rge. 17 (E) (W) _____
Name of Field: _____ Total Depth: 3385

I have this date completed supervision of plugging of:

Lease Name: J.L. Rumsey ~~Oil & Gas~~ Well No. 15
Operator's Full Name: Shell Oil Co
Complete Address: Box 744 Great Bend, Kans
Plugging Contractor: Forbes Casing Pulling Co
Address: Great Bend, Kans License No. 49
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____
Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No
If yes how long? _____ Reason: _____

Operation Completed: Hour 3PM Day 26 Month 5 Year 59

The above well was plugged as follows:
15" 120' circulated with cement - 10" 1096' circulated with 350 sax cement,
7" 3376' with 200 sax cement behind.
Pulled 2596' 7" to 700', circulated hole with heavy mud through 7" (26
sax Gel), displaced 30 sax cement through 7" at 450', heavy mud to
170', displaced 30 sax cement through 7" at 170', heavy mud to 30', set
rock bridge and 10 sax cement to bottom cellar.
Mudding and cementing by Forbes Co pump truck.

Signed: *Edwin Lester*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1959
06-01-59
CONSERVATION DIVISION
Wichita, Kansas