

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NW

SEC. 23 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 16 Lease Rumsey

Operator Great Bend Pipe & Supply Address Great Bend, Kans

Field _____ County Ellis

Total Depth 3505 Feet.

Plugging Contractor R & D Pipe Pulling Co

Plugging Contractor's License No. 236

Address _____

(Describe Briefly the manner in which the well was plugged)

16" at 130' circulated with cement - 10 3/4" 1118' circulated with
cement - 7" 3400' with 200 sax cement behind - 4 1/2" liner 3343' to 3505'
Filled with sand to 3300', set 5 sax cement with dump bailer - pulled
2623' 7" - filled hole with heavy mud (Gel) to 450', set rock and
20 sax cement - heavy mud to 250', set rock and 20 sax cement, heavy mud
to 30', set rock and 10 sax cement to bottom cellar.

Edna Petty
District Conservation Agent

Date 12-21-57

PLUGGING
FILE SEC. 23 T. 11 R. 17
BOOK PAGE 69 LINE 30

RECEIVED
STATE CORPORATION COMMISSION
DEPT. OF REVENUE
12-24-57
COR.