

15-051-05862-8000

Form CP-3
Rev. 6-26-62

10 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION

MAR 26 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Great Bend Pipe & Supply

Complete Address: Drawer (B) Great Bend, Kansas

Lease Name Rumsey Well No. 17

Location NW NW NE Sec. 23 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3387

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 1PM Day 22 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 1010' circulated with cement - 4 1/2" 3384' with 100 sax cement.

Sand to 3370', set 4 sax cement with dump bailer - pulled 2376' 4 1/2" to 500', circulated hole with heavy mud (20 sax Gel), displaced 20 sax cement through 4 1/2" - heavy mud to 240', displaced 20 sax cement through 4 1/2" - heavy mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 3/26/63

INV. NO. 6942-W

Signed: Edon Kelly
Well Plugging Supervisor

INVOICED