

RECEIVED  
CONSERVATION COMMISSION

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

OCT 9 1959  
10-09-59  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis  
Location: SW SW NE Sec. 23 Twp. 11 Rge. 17 (E) (W)  
Name of Field: \_\_\_\_\_ Total Depth: 3399

I have this date completed supervision of plugging of:

Lease Name: J.L. Rumsey ADB KC Well No. 20  
Operator's Full Name: Shell Oil Co  
Complete Address: Box 744 Great Bend, Kans  
Plugging Contractor: Forbes Casing Pulling & Halliburton Cementing  
Address: Great Bend, Kans License No. 49

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 12Noon Day 6 Month 10 Year 59

The above well was plugged as follows:

13" at 131' circulated with cement - 8 5/8" 1098' circulated with cement.  
4 1/2" 3390' with 100 sax cement behind.  
Filled with sand to 3380', set 3 sax cement with dump bailer, pulled 2600'  
4 1/2" to 500', circulated hole with heavy mud through 4 1/2" ( 15 sax Gel),  
displaced 20 sax cement through 4 1/2" at 500', heavy mud to 160', displaced  
20 sax cement through 4 1/2" at 160', heavy mud to 35', set bridge and 10  
sax cement to 0'

Mudding and cementing by Halliburton Cementing Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 1/8/60  
INV. NO. 237-W