

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1961
04-26-61
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis
Location: SE SE NE Sec. 23 Twp. 11 Rge. 17 (E) (W) _____
Name of Field: _____ Total Depth: 3431

I have this date completed supervision of plugging of:

Lease Name: J.L. Rumsey ANB VCC Well No. 25
Operator's Full Name: Shell Oil Co
Complete Address: Box 744 Great Bend, Kansas
Plugging Contractor: Forbes Casing Pulling
Address: Great Bend, Kansas License No. 49
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 18 Month 4 Year 61

The above well was plugged as follows:

a 5/8" 1145' circulated with cement - 4 1/2" 3422' with 100 sax cement.
Filled with sand to 3400', set 3 sax cement with dump bailer, pulled
2773' 4 1/2" to 460', circulated hole with heavy mud through 4 1/2" at 460'
(50 sax Gel), displaced 20 sax cement through 4 1/2" at 460', heavy mud to
150', displaced 20 sax cement through 4 1/2" at 150', heavy mud to 35', set
bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Forbes Co pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 5/10/61
INV. NO. 3057-W