

15-051-05868-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 123-17
LOCATION NW SW NE
SEC. 23 TWP. 11 RGE. 17 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 26 Lease J.L. Rumsey ANB RCC
Operator Shell Oil Co Address 434 N Oliver Wichita,
Field _____ County Ellis

Total Depth 3390' Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____
(Describe briefly the manner in which the well was plugged)

13" at 133' circulated with cement - 8 5/8" at 1095' circulated
with 325 sax cement - 4 3/4" at 3370' with 100 sax cement behind.
Pipe broke in, found mud at 3040', set sand and 4 sax cement
at 3040' - pulled 2600' 4 1/2" - filled hole with heavy mud to
300', set rock and 25 sax cement, mud to 35', set rock and 10
sax cement to bottom cellar.

District Conservation Agent
12-15-56

Date _____

PLUGGING
FILE SEC. 23 TWP. 11 R. 17 W.
BOOK PAGE 123 E. 17

12-17-56