

15-051-06264-00-01

CP-3

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name J. O. Forbes
Complete Address: Box 221 Great Bend, Kansas
Lease Name J.L. Rumsey ANBRCC Well No. 27
Location SE NW NE Sec. 23 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3432
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Forbes Casing Pulling Co
Address: Great Bend, Kansas License No. 49
Operation Completed: Hour 5PM Day 18 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 1134' circulated with cement - 4 1/2" 3420' with 100 sax cement 13" -131'
Filled with sand to 3490', set 4 sax cement with dump bailer - pulled 2400'
4 1/2" to 475' - circulated hole with heavy mud through 4 1/2" (17 sax Gel),
displaced 20 sax cement through 4 1/2" at 475', heavy mud to 180', set 20 sax
cement at 180', heavy mud to 35', cement to bottom cellar.
Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Eldon Kelly
Well Plugging Supervisor

DATE 9/23/62
INV. NO. 5412-W