

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

11-05-59

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: CSW NE Sec. 23 Twp. 11 Rge. 17 (E) (W)

Name of Field: Bemis Total Depth: ~~3336~~ 3449 AUB VCC

I have this date completed supervision of plugging of:

Lease Name: J.L. Rumsey AUB VCC Well No. 34

Operator's Full Name: Shell Oil Co

Complete Address: Box 744 Great Bend, Kans

Plugging Contractor: Forbes Casing Pulling

Address: Great Bend, Kans License No. ~~34~~ 49

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 2PM Day 28 Month 10 Year 59

The above well was plugged as follows:

16" 150' circulated with cement - 10 3/4" 1116' circulated with 1000 sax cement

7" 3422' with 200 sax cement - Baker packer at 3000', perforated 2863'

Filled with sand to 2850', set 5 sax cement with dump baler, pulled 2650'

7" to 850', circulated hole with heavy mud through 7" at 850' ( 30 sax Gel)

Displaced 30 sax cement through 7" at 500', heavy mud to 200', displaced

30 sax cement through 7" at 200', heavy mud to 30', set bridge and 10 sax

cement to bottom cellar.

Mudding and cementing by Forbes Co pump truck.

Signed: Jewel M. Ogden  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

Remarks:

INVOICED

DATE 1/14/60

INV. NO. 653-w