

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1962
08-24-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Great Bend Pipe & Supply
Complete Address: Drawer B Great Bend, Kans
Lease Name J.L. Rumsey Aug 62 Well No. 33
Location CNW NE Sec. 23 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3464
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: R & D Casing Pulling
Address: Hutchinson, Kansas License No. 236
Operation Completed: Hour 10AM Day 22 Month 8 Year 62

The Above well was plugged as follows:

16" 157' circulated with cement - 10" 1122' circulated with cement - 7" 3459' with 200 sax cement - 3" tubing lost in hole - top of tubing 2745', set plug at 2745' - sand and 5 sax cement - pulled 2340' 7" to 500', circulated hole with heavy gel mud through 7" at 500', (25 sax Gal), displaced 20 sax cement through 7" at 500', heavy mud to 180', set plug and 20 sax cement through 7" at 180', heavy mud to 30', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by R & D Company pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 8/28/62
INV. NO. 5581-W

Signed: [Signature]
Well Plugging Supervisor