

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-051-04879-0000

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Texaco Inc.,

Complete Address: 614 Bitting Bldg. Wichita, Kansas

Lease Name Henderson "B" Well No. 1

Location NW SE NW Sec. 22 Twp. 11 Rge. 18 (E) (W) X

County Ellis Total Depth 3485'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Comstock Pipe Pulling

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 11:30 A Day 15 Month 3 Year 1967

The Above well was plugged as follows:

Total Depth 3485' 8 5/8 csg set at 165 cwc.

5 1/2 csg set at 3482'

5 1/2 csg perf. 600' and squeezed to surface with 500 sc cement.

Filled with sand to 3475' and dumped 5 sc cement with dump bailer.

No pipe recovered. Filled with mud to 425'

Pushed plug to 425' and set rock bridge to 400'.

Dumped 3 yds readymix cement 400' to surface.

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1967

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3-17-67
INV. NO. 4917-w

Signed: Bro. P. Messing
Well Plugging Supervisor