

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Leo J. Dreiling Oil Co 15-051-19708-0000

Complete Address: Victoria, Kans

Lease Name Staab Well No. B-1

Location CN 1/2 NE SE Sec. 12 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3695

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: same & Sun Cementing Co

Address: License No.

Operation Completed: Hour 11AM Day 5 Month 6 Year 65

The Above well was plugged as follows:

8 5/8" 205' circulated with cement - 5 1/2" 3686' with 125 sax cement - DV tool set at 1396' and circulated with cement to bottom cellar.

Pumped 40 sax gel mud down 5 1/2" - pumped wiper plug followed by 70 sax cement - found top of cement at 2080' - filled hole with heavy rotary mud to 300', cement 300' to 0'.

I hereby certify that the above well was plugged as herein stated.

DATE 6/14/65

Signed: [Signature]
Well Plugging Supervisor

INV. NO. 1303-44

INVOICED