

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC - 9 1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051 - 21421 - 0000
CONSERVATION DIVISION
Wichita, Kansas (of this well)

Operator's Full Name Dreiling Oil, Inc.

Complete Address Rt #1, Victoria, Kansas 67671

Lease Name Ubert Well No. A-2

Location SW NW NE Sec. 12 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3647'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co. Tools by Sun Cementing Co.

Address _____ License No. 730

Operation Completed: Hour 11 A Day 7 Month 12 Year 1977

The above well was plugged as follows:

Total Depth 3647' 8 5/8 csg set 175' cwc 125 sk.

4 1/2 csg set 3510' cw 150 sk cem. with top perf. (3114')

Set plg 3100' -poured 50' sd -dumped 2 sk cem. W/dump bailer.

Cutoff & recovered 2908' of 4 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs

hull, followed with 70 sk 50-50 poz 2%, displaced with 5 sk gel & water &

capped with cementing plug & 50 sk 50-50 poz 2% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INDEXED

Signed: Leo Massey
Well Plugging Supervisor

DATE 12-12-77
INV. NO. 6348-W