

KANSAS

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

STATE CORPORATION COMMISSION
FEB 28 1972
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Hall "B" Well No. 12

Location SW NE NW Sec. 28 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3567' 34107 ANB

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 6:30 P Day 24 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 3567' 8 5/8 csg set at 1055' cwc 300 sk.

5 1/2 csg set at 3560' cw 100 sk cmt.

5 1/2 csg PBTB 3152' W/5 sk cal seal & 1 sk cmt.

5 1/2 csg squeezed at (1049-1100) with 150 sk cmt.

Ran 2" tubing to 3000' -displaced 25 sk cmt. (2740-3000)

Pulled tubing to 2760. circulated 25 sk gel & water. (520-2740)

Pulled tubing to 540' -circulated 75 sk cmt to surface.

Ran 3/4 tubing down annulus to 250' -circ. 25 sk cmt to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Murray
Well Plugging Supervisor

INDEXED

DATE 2/28/72

INV. NO. 5235-W