



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 123-10

LOCATION NE NE NW

SEC. 20 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. B-11 Lease Hall

Operator Cities Service Co Address Great Bend, Kans

Field Bemis County Ellis

Total Depth 3539 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1528' with 650 sax cement behind-5 1/2" at 3542'
with 100 sax cement behind - Baker plugs to 3440' sack cement,
chat to 3345', set 4 sax cement with dump bailer, pulled 1000'
5 1/2", filled hole with mud to 250', set rock and 15 sax cement
filled with mud to 35', set rock and 10 sax cement to bottom
cellar.

PLUGGING
FILE SEC 20 T 11 R 17
BOOK PAGE 125 LINE 10

DEC 21 1951

J. Edward Kelly
District Conservation Agent

12-21-51

Date 12-15-51