

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW NW

SEC. 26 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. B-1 Lease Hall

Operator Cities Service Co Address Great Bend, Kans

Field Bemis County Ellis

Total Depth 5399 Feet.

Plugging Contractor C. E. Shull

Plugging Contractor's License No. 8

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

15' at 104' circulated with cement - 10 3/4" at 1114' circulated  
with 400 sax cement - 7" at 5380' with 250 sax cement behind - 5 1/2"  
liner 5349' to 5589'.

Filled with sand to 5340', set 5 sax cement with dump bailer,  
pulled 2570' 7", filled with mud to 300', set rock and 25 sax cement,  
mud to 55', set rock and 10 sax cement to bottom cellar.

E. J. Lee  
District Conservation Agent

Date 3-26-54

RECEIVED  
MAR 29 1954  
03-29-54

**PLUGGING**  
FILE SEC 26 T 11 R 17W  
BOOK PAGE 22 LINE 13