

KANSAS

Handwritten initials

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Hall "B" Well No. 16

Location NE SE NW Sec. 26 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3617"

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11:45 A Day 1 Month 3 Year 1972

The above well was plugged as follows:

Total Depth 3617' 8 5/8 csg set at 1115' cwc 300 sk.

5 1/2 csg set at 3549' cw 110 sk cmt.

5 1/2 csg squeezed at 1161' W/100 sk cmt.

Set Limit plug at 2233'. No Pipe Recovered.

Ran 2" tubing to 2230' -displaced 12 sk gel & water W/100 lbs hulls and 20 sk

Halib.-Light cmt.

Pulled tubing to 590' -circulated 75 sk Halib.-Light cmt to surface.

Ran 3/4 tub. down annulus to 250' -circulated 30 sk cmt to surface. By HOWCO

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Red A. Murray*
Well Plugging Supervisor

DATE 3-6-72

INV. NO. 5290-W