



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 93-4
LOCATION CS 1/2 SE SW
SEC. 26 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. B-18 Lease Hall
Operator Cities Service Co Address Great Bend, Kans
Field Bemis County Ellis
Total Depth 5549 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1025' circulated with cement - 5 1/2" at 5479'

4ane Wells plugs to ~~2250~~ 5421' - perforations at 5250'.

Set bridge at 5225', sand and 5 sax cement set with dump bailer,

pulled 2950' 5 1/2", filled with mud to 300', set rock and 20 sax

cement, mud to 35', set rock and 10 sax cement to bottom

cellar.

RECEIVED
STATE CORPORATION COMMISSION

07-18-53
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 26 T 11 R 17
BOOK PAGE 23 LINE 4

Edward J. Kelly
District Conservation Agent
Date 7-7-53