

KANSAS

ll STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil company

Complete Address Box 553 Russell, Kansas 67665

Lease Name McCord "A" Well No. 16

Location SE SW NE Sec. 26 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3646'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11 A Day 2 Month 3 Year 1972

The above well was plugged as follows:

Total Depth 3646' 8 5/8 csg set at 1280' cwc 458 sk.

5 1/2 csg set at 3629' cw 175 sk cmt.

5 1/2 csg PBSD 3616' and perf. (3574-3578)

Set 5 1/2 wood plug at 3250' -poured 10' sd -Dumped 5 sk cmt W/dump bailer. (3200-3250)

Cutoff and recovered 2200' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug

and pumped 115 sk Halib.-Light cmt by HOWCO. SI pres. 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mussey
Well Plugging Supervisor

DATE 3-6-72

INV. NO. 5291-(W)