



15-051-20695-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Johnson of Gabbert - Jones Drlg. has this date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: Betorma Oil Co.

Complete Address: 603 Union Center Wichita, Ks.

Lease Name: Stackhouse Well No. 1

Location: NW SE SE Sec. 22 Twp. 13 Rge. (E)(W) 18

County: Ellis Total Depth 3680' Oil Well

Gas Well  Input Well  SWD Well  D & A XI Lost Hole

Mr. Johnson was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug ay 700' and displace  
40 sk cmt thru drill pipe. Heavy mud to 400' set cementing plug and  
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Ben F. Murrin  
Conservation Division Agent