



15:051-27428-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Dana Hewett of Emphasis Drlg. has this date requested permission to plug the following described well:

Operator's Full Name: Energy Reserves Group, Inc.

Complete Address: 925 Patton Rd. Great Bend, Kans.

Lease Name: Stackhouse Well No. #1 - "A"

Location: C - N¹/₂ - SW - SE Sec. 22 Twp. 13^S Rge. 18^W (E) (W)

County: Ellis Total Depth: 3638^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Hewett was instructed to plug the well as follows:
8 5/8" 146^{FE} SP. CUC w/ 70ST 50/50 Pozmix - 2% Gel - 3% Ca. Cl.
Order 110ST 50/50 Pozmix 4% Gel + 3% Ca. Cl. + 8 5/8" Plug.
Spot With Drill Stem - with Heavy Mud Between all Plugs.
1ST Plug @ 660^{FE} w/ 65ST Int
2ND Plug @ 210^{FE} w/ 30ST Int.
3RD Plug - Solid Bridge - Plug @ 40^{FE} to 0ST w/ 10ST Int.
5ST In Rat Hole

Very truly yours, By Halliburton Co.

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1931

CONSERVATION DIVISION
Wichita, Kansas

Marion Schmidt
Conservation Division Agent