



15:051:22226:00:00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Stan Ingreen of Reverie Drilling has this date requested permission to plug the following described well:

Operator's Full Name: Sid Tomlinson

Complete Address: Box 594 Twin Falls Idaho - 83301

Lease Name: Riedel Well No. "B" #2

Location: Q-5 1/2 - SE - SE - NE Sec. 31 Twp. 13 Rge. 19 (E) (W)

County: Ellis Total Depth: 3936 FT

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Ingreen was instructed to plug the well as follows:

8 5/8" 327 FT SB. CUC w/ 190 FT Cement - 2% Gel. 3% Co. Cl.  
Ordered 110 FT 50/50 Permox 6% Gel. + 8 5/8" Plug (Elev. 2277 FT)  
Spot with Drill Stem - with Heavy mud between all Plugs

1 FT Plug @ 840 FT w/ 40 FT Cnt.

2 FT Plug @ 300 FT w/ 25 FT Cnt.

3 FT Plug - Solid Bridge - Plug @ 40 FT w/ 10 FT Cnt.

5 FT In Cat Hole

Very truly yours, By: Halburton Cret

Missouri Schubert  
Conservation Division Agent

JAN 21 1981  
01-21-81  
CONSERVATION DIVISION  
Wichita, Kansas